

PROPOSED SPECIAL REPAIR FOR MCGS FY-2026-27 (11)

BOQ

Name of Contractor :

Date of Issue :

Date of Opening

Work : Karunawati House Replacing old Railing with New Railing Work

Work completion time - 35 Days

Total Estimated Cost - 2.20 Lakh

S.No.	Item	Unit	Quantity	Rate	Amount
Part A	Dismantling Work Civil / Repair Item				
1.1	Old Railing Dismantling Work	R.mt	49		
1.2	Dismantling of Kota stone/ Mosaic floor, Skirting Including C.conc Base upto 150mm to 200mm Depth laid in cement mortar up to thick ness75 mm (Kota + base material including stacking of material and disposal of unserviceable of material with in 50 Meter of lead)	Sq.mt	10		
1.3	Disposal of useful Kota stone/Useful item in material yard with in campus or Out Side Campus Lead-500 meter (Trolley size 10'x6' x1.5')100 Sqft per trolley.	Nos.	2		
1.4	Hole Making	Nos.	15		
1.5	Providing and fixing Kota Stone Flooring with Normal Polish , Kota stone slab flooring 30 to 40 mm thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1: 4 (1 cement : 4 coarse sand)	Sq.mt	10		
Part B	Fabrication work				
1	Providing and fixin MS Pipe Stair Railing as per Engineer Direction and Design	KG	1475		
Part C	Finishing Item				
1	Providing and fixin Distemping with 1st quality acrylic washable distemper (readymade) two or more coats of approved manufacturer and required shade and colour complete as per manufacturer's snecification with Scraping	Sq.mt.	95		
2	Providing and fixin Enamel Paint with 1st quality acrylic (readymade) two or more coats of approved manufacturer and required shade and colour complete as per manufacturer's snecification	Sq.mt.	85		
3	Providing and Fixing Primer (MS Iron and Wooden)	Sq.mt	85		
				Total=	
				GST 18%	
				G Total	
Note:	1.The rates for additional, altered and substituted work shall be paid as per BSR 2022 Ajmer @ % above/below.				
	2. The Total Amount of Security Deposit Shall be 5% (five percent) of the total value of the contract for the work & Defects Liability Period 12 months after completion of work				
	3 The samples of the material shall in either case have to be got approved from the Architect/Engineer.				